

**(A Govt. of India Enterprise)**  
**O/o Sub Divisional Engineer (E), B.S.N.L. Electrical Sub Division**  
**Head Post office complex BSNL CSC building Dharamshala 176215 .**  
**Tele No. 01892-222500, 9418038384 FAX 01892 222501**

No. SDE/E/BSNL/ESD/DMA/2016-2017/  
To

Dated: 14-07-2016

1. The Executive Engineer (E) B.S.N.L Electrical Division Shimla for information please.
2. M/s R.R. Electrical Electrical Co. V& P.O Kotkawal Teh. Distt Kangra (HP).
3. M/s Om Earth Movers, Sundernagar.
4. M/s G.S. Electrical Works Vill & P.O. Amb, Distt,. Una (HP).
5. M/S Goel Electric works , 80 P Road Feozpur ( Pb).
6. M/s. Perfect Engineers , 7 Doaba Market, opposite Bus Stand 17, Prakash Nagar Jalandhar.
7. Sharma Electric co. House No.-199, ward no.6 Hamirpur (HP).
8. M/s Rajindera Engineering works ist floor railway Gurudwara complex Gurdaspur Road Pathankot-145001
9. M/S Ravindera Enterprises opposite petrol pump main Bazar Ner Chowk Mandi (HP)
10. M/s Kumar Electric Co. Rajput Sabha Bhawan old bus stand kangra (HP).
11. Notice Board.

**Sub :- NIQ for the work:\_ Shifting & reinstallation of distribution Panel & other associated accessories at BTS station Sahu Talla district Chamba (HP)).**

**NOTICE INVITING QUOTATION**

The Sub Divisional Engineer (E) BSNL Electrical Sub Division Dharamshala invite on behalf of the Bharat Sanchar Nigam limited sealed quotation for the work mentioned above & as per schedule of work ( attached as annexure-A) The quotation documents can be obtained from the office free of cost on working days within office hours latest by 16-07-2016. The duly filled Quotation will be received up to at 3.00 P.M on dated 18-07-2016 and the same will be opened in this office (at Dharamshala) 3.30 P.M on the same day i.e 18-07-2016

**SPECIFICATIONS.**

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the qualified supervisor of the firm.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 3 days from the date of issue of work order.
5. The rate should be quoted inclusive of all taxes i/c Service tax.

Sub-Divisional Engineer (E)

<b>Name of work:- Shifting &amp; reinstallation of distribution Panel &amp; other associated accessories at BTS station Sahu Talla district Chamba (HP)</b>						
<b>S.No</b>	<b>Description Of Items</b>	<b>Qty</b>		<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1	Dismantling Distribution Panel, i/c disconnecting the power supply & electrical accessories / Associated work like cables energy meter complete as required at site	1	Job		Job	
2	shifting & Reinstallation of distribution panel & energy meter in the other room / suitable place in the existing BTS station at suitable place i/c making the connection by laying the cable on wall ceiling complete as required.	1	Job		Job	
3	Supplying & laying XLPE Aluminium conductor armoured cable of 1.1 KV grade of following sizes in the surface of wall etc. as required					
	a) 3.5 x 25sqmm	10	Mtrs.		Mtr	
4	Dismantling of 1.5 TR window type AC units ( Indoor & outdoor units ) i/c shifting the same in new equipment room i/c associated accessories from old equipment room complete as required.	2	Jobs		Job	
5	wiring for power plugs , AC units & light points with existing dismantled material complete as required at site	1	Job		Job	

Total Amount:- Rs.

Sub-Divisional Engineer (E)  
B.S.N.L. Elect. Sub-Division,  
Dharamshala (HP)

### **SPECIFICATIONS.**

1. Work shall be carried out as per CPWD/ BSNL specifications.
2. Work shall be supervised by the qualified supervisor of the firm.
3. Any damage done to the equipment / Bldg during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 7 days from the date of issue of work order.
5. The rate should be quoted inclusive of all taxes i/c Service tax.

Sub-Divisional Engineer (E)

