



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

**O/o Executive Engineer (E), B.S.N.L. Electrical Division
Head Post office Building, Near BSNL CSC building Dharamshala 176215 .
Tele No. 01892-223301, 227900**

NOTICE INVITING QUOTATION

Ltr. No.21(07) /EEE/BSNL/DMA/2017-18/339

Dtd. 23/08/2017

Name of work: Shifting, Installation , testing & commissioning of 63 KVA DEA at Telephone exchange building Jassur (HP)

Sealed quotations are hereby invited by the Executive Engineer (E),BSNL Electrical Division, Dharamshala for above mentioned work, as per schedule of work attached. Sealed quotation with your item rate should reach to the undersigned at 3.00 P.M on dated- 30/08/2017 and the same will be opened in this office at 3.30 P.M. on the same day i.e. on 30/08/2017.

TERMS /CONDITIONS:-

1. Work shall be carried out as per CPWD/BSNL specifications.
2. Work shall be supervised by the qualified supervision of the firm.
3. Any damage done to the equipment /building during the execution of work is to be made good by the contractor at his risk and cost.
4. Time allowed to carry out the work is 7 days from the date of issue of work order.

Executive Engineer(E)
BSNL Electrical Division,
Dharamshala(HP)

Copy to: -

1. M/s R.R. Electrical Co. V&P.O. Kitkawal, Dist. Kangra.(HP)
2. M/s Laxmi Enterprises, Sonapat.
3. M/s G.S. Electrical Works V. & P.O. Amb Dist. Una (HP)
4. M/s Goel Electric Works, Ferozpur (Pb)
5. M/s Perfect Engineers, Jalandhar (Pb)
6. M/s Sharma Electric Co., Hamirpur (HP)
7. M/s Gopal Krishnan Contractor, Chandigarh.
8. M/s Ravindra Enterprises, Mandi (HP)
9. M/s Kumar electric Co. Kangra (HP)
10. M/s Rajindra Engineering works, Pathankot (Pb)

E.E.(E), Dharamshala(HP)



BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

O/o Executive Engineer (E), B.S.N.L. Electrical Division
Head Post office Building, Near BSNL CSC building Dharamshala 176215 .
Tele No. 01892-223301, 227900

ANNEXURE 'A'

SCHEDULE

Name of Work:- Shifting , Installation , testing & commissioning of 63 KVA DEA at Telephone exchange building Jassur (HP)

S.N.	Description of Items	Qty	Rate	Unit	Amount
1	Dismantling & shifting of existing 150 KVA faulty DEA set from Engine room to suitable place at out side the DEA set room as per direction of Engineer in Charge i/c manual labour / tool & plant complete as required at site	1	Job	job	
2	dismantling / Carriage / transportation of existing , multicylinder water cooled electric start diesel Engine alternator set along with control panel and other associated accessories , of 63 KVA capacity , from Micro Wave station To telephone Exchange building at Jassur by suitable mean of transportation including loading and unloading etc. all complete as per direction of Engineer- in-charge	1	Job	job	
3	Installation, Testing & commissioning of 63 KVA DEA set on existing Foundation and AVM Pads i/c fixing of engine control panel , making connection with cable from alternator to Engine control panel , fuel line connection, fixing of Exhaust pipe / after necessary modification complete as required at site .	1	Job	job	
4	Replacement of following faulty items in the existing Engine instrument / control panel complete with interconnections, testing etc. all as required.				
	a) Solid state Battery Charger	1	No	Each	
	b) flexible hose pipe from Thermostate to radiator	1	NO	Each	
5	Servicing of following rating Engine coupled with alternator i/c replacement of lubricating Oil, lubricating Oil filter, diesel filter, cleaning of air filter, complete cleaning of the DEA set, testing on load etc. all as required.				
	a) 50/63 KVA	1	Jobs.	Job	

CONTRACTOR

Executive Engineer (E)
BSNL Electrical Division,
Dharamshala